

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. CW/2 SW SW

LOCATION SW/4

SEC. 1 TWP. 27 RGE. 13

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. Lease Nelumbo

Operator Shelly Oil Co Address Box #391 - Hutchinson - Kansas

Field County Pratt

Total Depth 4356 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 398 ft - Circulated with cement.
7" casing set at 4254 ft - Plugged back to near bottom &
3750 ft with Taper Wells P. sub sand & chat - Mixed
4 sacks cement at 3750 ft - Set off & pulled 7" casing -
filled with mud to 2560 ft - Set 16 1/2" bridge & 20 sacks of
cement at 2500 ft - Mixed to 20 ft - Bridge & 10 sacks
of cement at the surface

C. M. Stough -
District Conservation Agent

Date 12 - 20 - 48

PLUGGING
FILE SEC. 1 T 27 R 13 W
BOOK 75 LINE 27

DEC 22 1948
STATION
KANSAS