

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name TGT Petroleum Corp.

Complete Address 209 E William Wichita, KS

Lease Name Dunn Well No. 1

Location C. NE/SW Sec. 25 Twp. 27S Rge. 19 (E) (W) W

County Kiowa Total Depth 5025

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers Inc

Address Box 486 Ellinwood, KS License No. 462

Operation Completed: Hour 4:00 PM Day 27 Month 4 Year 1974

The above well was plugged as follows:

320 ft 8 5/8 surface cemented with 275 sacks. 4916 ft 4 1/2 long string
cemented with 140 sacks. Top perf. 4800 ft. Sand to 4780 ft. 4
sacks cement with bailer. Pulled 190 ft 4 1/2. Set 10 ft rock bridge
at 190 ft, 25 sacks cement. Mud to 40 ft, 10 ft bridge, 10 sacks
cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 5/8/74
INV. NO. 9043-W