

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 097-20, 643⁻⁰⁰⁰⁰ (of this well)

Operator's Full Name Gulf Oil Exploration & Production Co.

Complete Address Box 2093-Wichita, Ks. 67201

Lease Name Einsel Well No. 2-36

Location C NW SW Sec. 36 Twp. 27s Rge. 19 (E) (W) X

County Kiowa Total Depth 5054

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor Daco Lease & Well Servicing Co.

Address Drawer 3010, Borger, Texas. 79007 License No. 138

Operation Completed: Hour 2:30 Day 16 Month 10 Year 1980

The Above well was plugged as follows:

417' 8 5/8" casing w/200 sax cement. 5 1/2" casing set at 5053' w/300
sax cement. Plug back to 5008'-Pref's at 4926'-28-4796'-4836'-top pref
4270'-4410'-CIBP'S at 4900'-4772'-Daco mixed & pumped in 5 1/2" casing
75 sax common cement to 4700'-Top bridge plug at 3992'-Pull 2586'
casing-Daco mixed & pumped through 5 1/2" casing, cement at 1300'-35 sax-
400'-35 sax-Bridge at 40' & 10 sax cement to 5' below G1. All cement
plugs was loaded between plugs w/heavy mud.

RECEIVED
STATE CORPORATION COMMISSION
10-20-80
OCT 20 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well-Plugging Supervisor
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 11-18-80
INV. NO. 3610-U