

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 321 West Douglas, Wichita, Kansas

Lease Name Parton Well No. # 2

Location C NE SE Sec. 3 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 4410

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No.

Operation Completed: Hour 7:30PM Day 10th Month June Year 1964

The Above well was plugged as follows:

316' of 8 5/8" surface pipe, cemented with 300 sacks. Fluid level was
up in the hole. 1st cementing plug and 1/2 sack hulls was pushed to 275',
and cemented with 25 sacks, through the drill pipe. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 10 sacks to base of the cellar.
Rat and mouse hole bridged and cemented with 5 sacks.
This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/11/64

INV. NO. 9290-W

Signed: Archie Elving
Well Plugging Supervisor