

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name Koelsch Well No. # 1

Location C NE SW Sec. 3 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 4936'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:15PM Day 9th Month Dec. Year 1966

The Above well was plugged as follows:

337' of 9 5/8" surface pipe, cement circulated. 4935' of 5 1/2" long string,
cemented with 100 sacks. Plug back T.D. 4820'. Top perferation 4810'.
Bottom of the hole was sanded to 4800', and cemented with 5 sacks, through
the dump bailer. 3581' of 5 1/2" long string was recovered from the hole.
Fluid level in the hole was at 315', bridge plug and rock bridge from
315' to 305', and cemented with 25 sacks. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/28/66 pd

INV. NO. 4333-W