

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-5-76
JAN 5 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum Inc

Complete Address Route 2 Great Bend, KS

Lease Name Kerr Well No. 1

Location App. C NE/NW Sec. 10 Twp. 27 Rge. 19 (E) (W)

County Kiowa Total Depth 4938

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Pratt Well Service Inc

Address 723 S Minnescah Pratt, KS License No. _____

Operation Completed: Hour 9:00 AM Day 2 Month 1 Year 1976

The above well was plugged as follows:

333 ft 8 5/8 surface cemented with 250 sacks. 4936 ft 5 1/2 long string
cemented with 210 sacks. Top perf. 4242 ft. Sand to 4200 ft, 5 sacks
cement with bailer. Pulled 2300 ft 5 1/2. Pump 2 sacks hulls, 10 sacks
gel, 100 sacks cement to surface.

Pumped by Sun Cementing Great Bend, KS

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1-5-76

Signed: [Signature]
Well Plugging Supervisor

INV. NO. 2504-W