

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-14-66
MAR 14 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Gas Marketing, Inc.

Complete Address: Box 159, Stafford, Kansas

Lease Name Davis Well No. # 1

Location C NW NE Sec. 10 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 5030'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 4:30PM Day 11th Month March Year 1966

The Above well was plugged as follows:

321' of 8 5/8" surface pipe, cement circulated. 4845' of 4 1/2" long string,
cemented with 150 sacks. Plug back TD 4500'. Top perferation 4334'. Bottom
of the hole was sanded to 4300', and cemented with 3 sacks. 3550' of 4 1/2"
long string was recovered from the hole. Fluid in the hole was bailed down
to 330', rock bridge from 330' to 320', and cemented with 25 sacks. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented with
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/14/66
INV. NO. 2855-U