

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-9-76
MAR 09 1976

J. Lewis Brock
Administrator
245 North Market
Wichita, Kansas 67202

CONSERVATION DIVISION
API Number 15 - - Wichita, Kansas (of this well)

Operator's Full Name Pickrell Drlg Co

Complete Address 205 Litwin Bldg Suite 205 Wichita, KS

Lease Name Davis J Well No. 1

Location NE/SW Sec. 10 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 4945

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Co

Address Chase, KS License No. 683

Operation Completed: Hour 11:00 PM Day 6 Month 3 Year 1976

The above well was plugged as follows:

319 ft 8 5/8 surface cemented with 225 sacks. 4445 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4363 ft. Sand to 4350 ft, 4
sacks cement with bailer.. Pulled 3550 ft 4 1/2. Pump 2 sacks hulls,
10 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-09-76

INV. NO. 2869-W

Signed: Russell B. ...
Well Plugging Supervisor