

15-0971-20035-0000

Form CP-3  
Rev. 6-26-62

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT -2 1967  
10-2-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed September 19, 1967.

Operator's Full Name Gabbert-Jones, Inc.  
Complete Address: 830 Sutton Place, Wichita, Kansas 67202  
Lease Name Ernest Davis Well No. # 1  
Location C N/2 NE Sec. 10 Twp. 27 Rge. 19 (E) (W) W  
County Kiowa Total Depth 4833'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Gabbert-Jones, Inc.  
Address: 830 Sutton Place, Wichita Kansas 67202 License No. \_\_\_\_\_  
Operation Completed: Hour 8:30PM Day 29th Month Sept. Year 1967

The Above well was plugged as follows:

333' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid level  
in the hole was at 200', 1st cementing plug and 1/2 sack of hulls was pushed  
in fluid to 300', and cemented with 25 sacks, through the drill pipe, with  
cement from 300' to 225'. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented  
with 10 sacks, with cement from 30' to the base of the cellar. Rat and  
mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

**INVOICED**  
DATE 10/2/67  
INV. NO. 6419-W