

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,154 ⁰⁰⁰¹

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name D. W. B. Drilling Inc.

Complete Address 515 R.H. Garvey Bldg Wichita, Kansas 67202

Lease Name Millers Well-No. 1

Location C-NE-NW Sec. 5 Twp 27S Rge. 19W (East)(West)

County Kowa Total Depth 4840

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated abandoned oil well

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 681

Operation Completed: Hour: 2:30 PM Day: 13 Month: November Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 363' of 8.56" surface casing cemented with 225 lbs cement and 4839' of 4 1/2" production pipe in hole cemented with 200 lbs of 50/50 sparse cement. The perforations are from 4775' to 4806'. 1st plug sanded off bottom to 4700' with 4 sbx cement. 2nd plug 1100' with 5 sbx hulls & 5 sbx of Jell and 70 sbx cement. 3rd plug 5 sbx hull 2 sbx Jell then release rubber plugs 360' then 40 sbx of cement on top of rubber plug. 4th plug 40' to 0' with 1 sbx hulls & 10 sbx of cement. Plugging ~~was~~ accomplished by ^{Halliburton} ~~James~~ Cementing Great Bend Kans.

There was 2450' of 4 1/2" pipe recovered, shut in pressure 650 lbs

I hereby certify that the above plugging instructions were given as herein stated.

NOV 12 10 81

NOV 17 1981
11-17-81

Signed: Paul Luttich
Conservation Division Agent

INV. NO. 8609W

CONSERVATION DIVISION
Wichita, Kansas

157.30