

State of Kansas



15-185-21123-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Freeman Drlg. Co., Inc. has this date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Ram Petroleum Co.

Complete Address: 800 Vickers, Wichita, Kansas

Lease Name: Galloway Well No. 1

Location: SW SW NW Sec. 19 Twp. 24 Rge. 12 ~~(E)~~ (W) X

County: Stafford Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

Fill hole with mud and spot 30 sx cement at 480'.

Fill hole with mud and spot 30 sx cement at 300'.

Fill hole with mud to 40' and 1/2 sx hulls, plug, and

10 sx cement. 10 sx cement in rat & mouse holes.

327' of 8 5/8" surface casing cement circ.

Very truly yours,

Duane Rankin
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1980
7-16-80
CONSERVATION DIVISION
Wichita, Kansas