

State of Kansas



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

7-16-62  
 JUL 16 1962

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date 7-11-1962, 1961, authorized the following plugging operation:

Operator's full Name: Imperial Oil of Kansas, Inc.

Complete Address: Box 97 Wakeeney, Kansas

Lease Name: Miller Well No. 1

Location: Gen. SW NW Sec. 33 Twp. 27S Rge. 19 (E)(W) X

County: Kiowa Total Depth: 4897'

Oil Well  Gas Well  Inlet Well  SWD Well

D & A  Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

360' of 8 5/8" surface pipe. Heavy drilling mud to 550',  
1/2 sack hulls, first cementing plug and 20 sacks cement  
through drill pipe. Filled with heavy drilling mud to 350'.  
1/2 sack hulls and second cementing plug 15 sacks cement.  
Hole filled to 40'. Third cementing plug. and 1/2 sack hulls  
 and 10 sacks cement. Bridge Very truly yours,  
 and 2 sacks cement in  
 rathole.

*Herman Gustus*

