

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-20,113-0000

LEASE NAME SHEEGOG

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 2 TWP. 27S RGE. 13 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Bowers Drilling Co., Inc.

ADDRESS 125 No. Market

PHONE#(316) 262-6449 OPERATORS LICENSE NO. 5435

Date Well Completed 2-19-69

Character of Well Oil (depleted)

Plugging Commenced 8-5-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-6-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? no If not, is well log attached? Yes

Producing Formation Lansing KC Depth to Top 3755 Bottom 4075 T.D. 4400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Claya& shale	0	423	8-5/8"	423	0
Lansing KC	Oil & Water	3755	4075	4-1/2	4400	1800
Perf. 3295 --S	Squeezed w/300 sax cement,	top 3100'. Plug back TD 3638				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled w/ sand to 3075', dumped 4 sax cement. Plug w/100 sax cement & 3 sax hulls, pumped in to surface. Max. press. 300#. SIP 100#. Used BJ Titan light cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. \_\_\_\_\_

Address Medicine Lodge, Kansas 67104

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Emil E. Bowers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 86

Judy C. Ridder  
Notary Public

My Commission Expires: March 2, 1988

JUDY C. RIDDER  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY APPT. EXP. 3/2/88

AUG 25 1986

Form CP-4  
Revised 08-84

WELL LOG

BOWERS DRILLING COMPANY, INC.

COMPANY:  
CONTRACTOR:  
WELL:  
LOCATION:

Bowers Drilling Company, Inc.  
Bowers Drilling Company, Inc.  
Sheegog No. 1  
SW NW SE Section 2-278-13W  
Pratt County, Kansas  
January 20, 1969  
February 2, 1969  
1931 Kelly Bushing

COMMENCED:  
COMPLETED:  
ELEVATION:

0 - 200 Shale and sand  
200 - 1747 Shale and shells  
1747 - 3870 Lime and shale  
3870 - 3965 Lime  
3965 - 4020 Lime and shale  
4020 - 4287 Lime  
4287 - 4311 Sand and shale  
4311 - 4400 Lime and shale  
4400 T. D.

Driller: (Name)  
Location of well

**LOG TOPS:**

Topoka	3221	Mississippian	4174
Heebner	3559	Viola	4229
Douglas	3599	Simpson	4260
Brown Lime	3723	Simpson Dolomite	4279
Lansing	3752	Simpson Sand	4294
Base/Kansas City	4075	Arbuckle	4374

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sheegog No. 1 located SW NW SE Section 2-278-13W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*  
Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, this 6th day of February, 1969.

Sherry Gish, Notary Public

My commission expires June 30, 1971

Further affidavit with not,

(S) *Emil E. Bowers*

Subscribed and sworn to before me this 6th day of February, 1969

RECEIVED  
NOTARY PUBLIC

My Commission expires June 30, 1971

NO 8-25-86

AUG 25 1986