

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

P R A T T

County. Sec. 2 Twp 27 Rge 13 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NE SE

Lease Owner Crane-Jocelyn and Varn

Lease Name Harrel Well No. 1

Office Address 407 Brown Building---Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 28 1954

Application for plugging filed June 30 1954

Application for plugging approved July 1 1954

Plugging commenced June 29 1954

Plugging completed July 3 1954

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4389 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	349	None
				5 1/2"	4350	3314

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4020 feet to 3889 feet for each plug set.

Put in rocks and dump 5 sacks of cement, top off cement at 3854 feet.

Shot casing off at 3300'

Pulled pipe out of hole. Pumped in 25 sacks aquagel and 100 sacks of cement in surface casing.

RECEIVED
STATE CORPORATION COMMISSION
7-9-54
JUL 9 1954
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Forbes Casing Pulling Company
Address Box 221----Great Bend, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.
J. E. Selby (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. E. Selby

Pratt, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of July, 1954

Maudie B. McBride
Notary Public.

My commission expires June 30, 1955.

23-8390-s 6-51-20M
PLUGGING
FILE SEC 2 T 27 R 13W
BOOK PAGE 45 LINE 26

9/14/2

DRILLERS' LOG
HARREL # 1, Pratt County, Kansas

0-60

Clay

60-120	Sand
120-249	Shale & Shells
249-970	Red Sed. Shale & Shells
970-1600	Shale & Shells
1600-1723	Salt
1723-1920	Shale & Lime
1920-2015	Lime
2015-3115	Shale & Lime
3115-3330	Lime
3330-3720	Shale & Lime
3720-4178	Lime
4178-4209	Lime & Chert
4209-4232	Chert, Shale & Iron Pyrite
4232-4234	Lime & Chert
4234-4252	Shale, Lime & Chert
4252-4267	Chert & Shale
4267-4290	Sand
4290-4323	Coring
4323-4349	Shale & Lime
4349-4379	Lime, Sand & Shale
4379-4389	Shale & Lime
4389	TOTAL DEPTH

(over)

I certify that the above is true and correct as being taken from the daily drilling reports of the HARREL #1.

J. E. Selby
J. E. Selby-Bookkeeper
SCHAFER DRILLING COMPANY

STATE OF KANSAS, COUNTY OF PRATT, SS:

Subscribed and sworn to before me this 20th day of April, 1954.

Velda Coulter
Notary Public

my commission expires February 25, 1955.

RECEIVED
STATE COM. OF GEO. COMMISSION

JUL 1 1954

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC	27	R 13W
BOOK	PAGE	45	LINE 26