


15-151-10268-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec 1 Twp 27S Rge 13 (E W) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE SW SW
Lease Owner Lindsley Drilling Company et al
Lease Name Helmke Well No. 1
Office Address 1001 Union Natl. Bk. Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/29/51 19
Application for plugging filed 8/29/51 19
Application for plugging approved 8/29/51 19
Plugging commenced 8/29/51 19
Plugging completed 8/29/51 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation None Depth to top Bottom Total Depth of Well 4402 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	N-O-N-E					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

First Plug 253' w/ 20 Skts. Cement
Second Plug 30' w/ 5 Skts. Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lindsley Drilling Company
Address 1001 Union Natl. Bk. Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robt. K. Lindsley (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robt. K. Lindsley, Partner
1001 Union Natl. Bk. Bldg., Wichita 2, Kan

SUBSCRIBED AND SWORN to before me this 31st day of August, 19 51

My commission expires Sept. 18, 1952

Notary Public

23-8390-s 6-51-20M

PLUGGING
FILE SEC 1 T 27 R 13w
BOOK PAGE 166 LINE 24

SEP 1 X 1951 RCD 9-1-57
CONSERVATION DIVISION

Helmke #1

NE SW SW
Sec. 1-27S-13W
Pratt County, Kansas
Ele. 1894 DF
1891 Gr

Contractor: Lindsley Drilling Company
Started August 10, 1951 Finished August 29, 1951

LOG

Sand	0	-	65	
Sand & Clay	65	-	140	
Red Bed & Shells	140	-	264	Set 8-5/8 @ 264'
Cement-Red Bed-Shells	264	-	435	
Red Bed	435	-	620	
Sand & Red Bed	620	-	825	
Shale & Shells	825	-	1000	
Shale & Lime	1000	-	1575	
Shale & Lime	1575	-	1840	SLM @ 1500' - O.K.
Sandy Lime	1840	-	1950	
Lime & Shale	1950	-	2400	SLM @ 2000' - O.K.
Lime & Shale	2400	-	2720	SLM @ 2500' - O.K.
Shale	2720	-	3010	
Shale & Lime	3010	-	3270	Strapped drill pipe
Lime	3270	-	3465	
Broken Lime	3465	-	3625	
Lime & Shale	3625	-	3730	
Lime	3730	-	3810	
Lime & Shale	3810	-	3930	
Lime	3930	-	4005	
Lime & Shale	4005	-	4075	
Lime	4075	-	4117	
Lime & Shale	4117	-	4160	
Chert & Lime	4160	-	4252	
Sand-Shale-Chert	4252	-	4265	
Chert & Sand	4265	-	4292	
Shale & Lime	4292	-	4402	TD D&A

TOPS:

Lansing	3725
Mississippi	4077
Kinderhook	4118
Viola	4142
Simpson Shale	4226
Arbuckle	4338 D&A

State of Kansas)
) SS.
County of Sedgwick)

RECEIVED
STATE CORPORATION COMMISSION
SEP 1 X 1951
CONSERVATION DIVISION
Wichita, Kansas

I, Robt. K. Lindsley, do hereby certify that the above is a true and accurate log of the Helmke #1 well, located in the NE SW SW of Section 1-27S-13W, Pratt County, Kansas.

Robt. K. Lindsley
Robt. K. Lindsley, Partner

Subscribed to and sworn before me this 31st day of August, 1951.

Una A. McKenzie
Notary Public

My Commission Expires September 18, 1952.

PLUGGING
FILE SEC 1-27-13W
BOOK PAGE 106 LINE 24