

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County. Sec. 1 Twp. 27 Rge. (E) 13 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines.

Lease Owner. Tuesday Oil Company

Lease Name. Calbeck Well No. 1

Office Address. 801 Milan Building, San Antonio, Texas.

Character of Well (completed as Oil, Gas or Dry Hole). dry hole

Date well completed. 19

Application for plugging filed. 19

Application for plugging approved. 19

Plugging commenced. October 12, 19 44

Plugging completed. October 21, 19 44

Reason for abandonment of well or producing formation. dry hole

If a producing well is abandoned, date of last production. dry hole 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well. W. H. Kerr, Great Bend, Kansas.

Producing formation. none Depth to top. Bottom. 4227 Total Depth of Well. 4253 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water		4227	7" O.D.	4223	3069.79
Surface	Water	0	432	10 1/2"	432	Left In.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom of hole plugged back with sand to 4000'.
Dumped 5 sacks of cement with dump bailer, on top of sand.
Cut casing at 3500' would not pull, cut 3069' pulled casing filled hole with mud. Bridged hole at bottom of surface casing dumped 10 sacks of cement on top of bridge. Filled 10' surface casing with dirt. Cemented top of surface casing with 5 sacks of cement.

PLUGGING
FILE 1-27-R134
BOOK PAGE 136 LINE 37

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Tuesday Oil Company

Address. 801 Milan Building San Antonio, Texas.

STATE OF Kansas COUNTY OF McPherson

Don W. Canfield (employee of owner) or

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don W. Canfield

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of Nov. 19 44.

My commission expires My Commission Expires Sept. 14, 1946

Notary Public.

COMPANY: Tuesday Oil Company
CONTRACTOR: Hannum Drilling Company, Inc.
FARM: Calbeck Well No. 1

LOCATION: c. NW/4 NE/4
Section 1-27-13W
Pratt County,
Kansas

COMMENCED: September 11, 1942
COMPLETED: October 2, 1942 (Rotary Hole)


ELEVATION: 1908'
PRODUCTION:

CASING RECORD

10 3/4" 432' - 320 sacks
7" 4223' - 100 sacks

FORMATION	DEPTH	FORMATION	DEPTH
surface clay	25	lime & shale	4095
sand	135	chert & lime	4019
red rock & sand	180	shale	4145
sand	230	chert	4210
red rock & sand	405	shale & sand	4217
red rock & shells	735	shaly sand	4224
anhydrite	780	sand - show oil	4227
sand	835		
red rock, shale & shells	1060		
shale & shells	1240	total depth - rotary hole	4227
shale, shells, salt	1405		
shale & shells	1495		
shale, shells & anhydrite	1585		
shale, shells	1725		
anhydrite	1950		
lime & shale	2070		
sandy lime	2250		
broken lime & shale	2770		
sand	2782		
broken lime & shale	2875		
broken lime	2905		
lime, sandy	2985		
broken lime & shale	3055		
broken lime	3195		
lime	3435		
broken lime & shale	3460		
sandy lime & shale	3500		
broken lime & shale	3520		
broken lime	3539		
shale & lime	3711		
lime	3765		
lime (cherty)	3805		
lime	3815		
lime, (soft)	3848		
lime (cherty)	3871		
soft lime	3875		
lime	3980		

PLUGGING
FILE 1-27-13W
BOOK 16-136 LINE 37



I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling reports.

J. M. Hannum

Subscribed and sworn to before me this 15 day of February, 1943

Clyttell Smalley
Notary Public

My Commission expires: December 6, 1945