


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 33 Twp. 27S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Imperial Oil Company

Lease Name MILLER Well No. 1

Office Address 780 Fourth Natl. Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed July 11, 1962 19__

Application for plugging filed July 11, 1962 19__

Application for plugging approved July 11, 1962 19__

Plugging commenced July 11, 1962 19__

Plugging completed July 11, 1962 19__

Reason for abandonment of well or producing formation
No commercial quantities of oil found

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4897 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	8-5/8" at 361'	not pulled			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 550' with 20 sacks cement

Set second plug at 350' with 15 sacks cement

Set top plug at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1962
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address Box 97, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John Lehman (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman
780 Fourth Natl. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of July, 19 62

My commission expires July 5, 1966

Bette J. Silcott
Bette J. Silcott Notary Public.

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

MILLER NO. 1
C SW NW Sec. 33-27S-19W
Kiowa County, Kansas

Total Depth: 4897'

Elevation: 2267 K.B.
Production: Dry

Commenced: 6/25/62 Completed: 7/11/62

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8 " surface pipe at 361' with 300 sacks cement.

Figures indicate bottom of formations:

TOPS

Sand & Shale	642'	Heebner	4074 (-1807)
Anhydrite	657'	Toronto	4095 (-1828)
Shale & Shells	1230'	Douglas	4108 (-1841)
Anhydrite	1250'	Brown Lime	4229 (-1962)
Shale & Shells	2470'	Lansing-Kansas City	4236 (-1969)
Lime & Shale	4025'	Base Kansas City	4593 (-2326)
Lime	4851'	Cherokee Shale	4747 (-2480)
Chert	4855'	Mississippi (Osage)	4836 (-2569)
Lime & Chert	4897'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh
Raymond R. Dombaugh

Subscribed and sworn to before me this 18th day of July, 1962.

My commission expires:

July 5, 1966

Bette J. Silcott
Bette J. Silcott, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1962

CONSERVATION DIVISION
Wichita, Kansas