

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kiowa SEC. 36 TWP. 27 SRGE. 19W E/W  
Location as in quarters or footage from lines:  
C SE SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner TGT Petroleum Corp.  
 Lease Name EINSEL 'E' Well No. 1  
 Office Address 209 E. William, Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed August 1, 1981  
 Application for plugging filed August 1, 1981  
 Plugging commenced August 1, 1981  
 Plugging completed August 1, 1981  
 Reason for abandonment of well or producing formation No commercial quantity of oil gas encountered.  
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4875'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 1200' with 70 sx.  
Set 2nd plug @ 700' with 35 sx.  
Set 3rd plug @ 350' with 25 sx.  
40' Solid Bridge with 10 sx.  
5 sx. in Rathole. 50-50 posmix, 3% c.c.  
Plug was down @ 1:30 a.m., 8/01/81

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.  
 Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS  
 (Address) 67202

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1981

My Commission expires: 7-13-85

Elizabeth G. Terry Notary Public  
 RECEIVED  
 STATE CORPORATION COMMISSION  
8-7-81  
 AUG 7 1981  
 CONSERVATION DIVISION  
 Wichita Kansas



CONTRACTORS WELL LOG

OPERATOR: TGT Petroleum Corp.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: EINSEL 'E' #1  
 LOCATION: C SE SE, Sec. 36-27S-19W  
 Kiowa County, Kansas  
 SPUD DATE: 7/14/81  
 COMPLETION DATE: 8/01/81

0	96	Clay, Sand, & Shale
96	718	Sand & Shale
718	810	Shale
810	1250	Shale & Sand
1250	3945	Shale
3945	4200	Shale & Lime
4200	4466	Lime
4466	4650	Shale & Lime
4650	4875	Lime
	4875	Rotary Total Depth

Spud hole @ 8:15 p.m., 7/14/81. Drilled 718' of a 12½" hole. Ran 17 joints of 8 5/8" 24# casing set @ 715' K.B. Cemented with 400 sx. of Halliburton Lite, 100 sx. of common 2% gel, 3% c.c. Pumped plug to 680' K.B. Cement did circulate. Plug was down @ 4:30 p.m., 7/15/81.

4875' TD. Set 1st plug @ 1200' with 70 sx. Set 2nd plug @ 700' with 35 sx. Set 3rd plug @ 350' with 25 sx. 40' Solid Bridge with 10 sx. 5 sx. in Rathole, 50-50 posmix, 3% c.c. Plug was down @ 1:30 a.m., 8/01/81.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the EINSEL 'E' #1, C SE SE, Sec. 36-27S-19W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of August, 1981.

Elizabeth G. Terry  
 Elizabeth G. Terry  
 NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 7 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

