

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20776-0000

LEASE NAME Einsel "F"

WELL NUMBER 1

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 27 SRGE. 19 (X) (W)

COUNTY Kiowa

Date Well Completed 8/26/81

Plugging Commenced 3/01/01

Plugging Completed 3/05/01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 7570 -W. 21st-Bldg. 1010-D. Wichita, Ks. 67205

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top 4799' Bottom 4803' T.D. 4823'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	710'	None
				4 1/2"	4822'	2603'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sand off bottom to 4400'. Set 4 sx cement; pump 8 sx gel & 50 sx cement at 1200'; pump 50 sx cement at 740'; pump 10 sx at 40'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D. Wichita, Ks. 67205

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp. APR 13 2001

STATE OF Kansas COUNTY OF Sedgwick, ss. 4-13-2001

B. Lynn Herrington (Employee of Operator) of (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D

Wichita, Ks. 67205

Subscribed AND SWORN TO before me this 12th day of April, 2001

Judith K. Moser Notary Public

My Commission Expires: May 17, 2001



RECEIVED

SEP 10 1981

CONTRACTORS WELL LOG

OPERATOR: TGT Petroleum Corp.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: EINSEL 'F' #1
 LOCATION: C SE NE, Sec. 36-27S-19W
 Kiowa County, Kansas
 SPUD DATE: 8/06/81
 COMPLETION DATE: 8/26/81

0	200	Sand & Shale
200	611	Sand & Shale
611	715	Shale
715	1045	Sand & Clay
1045	3489	Lime & Shale
3489	3600	Shale
3600	3757	Lime & Shale
3757	3868	Lime
3868	4060	Lime & Shale
4060	4100	Lime
4100	4197	Shale & Lime
4197	4285	Lime & Shale
4285	4360	Lime
4360	4490	Lime & Shale
4490	4533	Lime
4533	4762	Lime & Shale
4762	4788	Lime
4788	4798	Lime & Shale
4798	4808	Lime
4808	4823	Lime & Shale
	4823	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 APR 13 2001
 CONSERVATION DIVISION
 Wichita, Kansas

Spud hole @ 8:00 p.m., 8/06/81. Ran 20 jts. of 8 5/8" 24# casing set @ 710.61' and cemented with 400 sx. Halliburton Lite followed with 100 sx. common 3% c.c 2% gel. Plug was down @ 3:15 a.m., 8/08/81. Cement did circulate.

4823' TD. Ran 119 jts. of 4 1/2" 10 1/2# casing set @ 4822' and cemented with 75 sx. of Halco Lite, 12 1/2# Gilsinite per sack. Followed with 200 sx. of 50-50 posmix, 10% Salt. Job complete @ 3:00 a.m., 8/26/81.

SAMPLE TOPS:

Anhydrite 1141'
 B/Anhydrite 1173'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of th EINSEL 'F' #1, C SE NE, Sec. 36-27S-19W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres

Subscribed and sworn to before me, a notary public, in and for the aforesaid county and state as of this 3rd day of September.



Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my Commission Expires 7-13-85