

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

R

NORTH

			x

Locate well correctly on above
Section Plat

Kiowa County, Sec. 3 Twp. 27S Rge. (E) 19(W)
 Location as "NE/CNW%SW%" or footage from lines C NE NE SE
 Lease Owner Sunray Mid-Continent Oil Company
 Lease Name Parton Well No. 1
 Office Address 321 West Douglas - Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry
 Date well completed November 9 19 60
 Application for plugging filed November 11 19 60
 Application for plugging approved November 15 19 60
 Plugging commenced November 11 19 60
 Plugging completed November 11 19 60
 Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. LacKamp
 Producing formation None Depth to top Bottom Total Depth of Well 5017 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Water	4786	4886	8-5/8	325	0
Kinderhook	Dry	4906	4918	5-1/2	4999	2500
Viola	Water	4978	T.D.			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 25 sacks cement into perforations at 4789-4802'.
 Filled hole with mud and set plug at 310' -- 10' of rock and
 20 sacks cement. Filled with mud to 40' and then 10' of rock
 and 10 sacks of cement to surface. Welded steel plate over
 surface pipe.

RECEIVED
 STATE CORPORATION COMMISSION
 12-30-60
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
 Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 Nash A. Gough (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nash A. Gough
 321 W. Douglas - Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 60

My commission expires July 13, 1963 Notary Public.




WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HILTON DRILLING CO.
Farm- Parton No. 1

SEC. 3 T. 27 R. 19W
NE NE SE

Total Depth. 4862'
Comm. 1-31-59 Comp. 2-21-59
Shot or Treated.
Contractor. Hilton Drlg. Co.
Issued. 4-25-59

County Kiowa
KANSAS



CASING:

8 5/8" 325' cem w/225 sx.

Elevation. 2259' DF

Production. Dry

Figures Indicate Bottom of Formations.

shale	530
sand	570
red bed	670
gypsum	690
red bed	1250
Anhydrite	1275
shale	1920
lime & shale	2280
lime	2760
lime & shale	2840
lime	3030
lime & shale	3130
lime	3215
lime & shale	3340
shale	3415
lime & shale	3595
lime	4081
shale	4090
lime & shale	4191
lime	4565
lime & chert	4588
shale & lime	4629
lime	4728
lime & shale	4764
lime	4770
shale & sand	4775
lime	4778
chert	4806
lime & chert	4862
Total Depth	

TOPS: SCOUT

Heebner	4043
Toronto	4067
Douglas	4080
Brown Lime	4191
Lansing	4199
Base Kansas City	4540
Marmaton	4545
Mississippi	4778