


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County. Sec. 10 Twp. 27 Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines Center of NW to NE
Lease Owner Gas Marketing, Inc.
Lease Name Davis "R" Well No. 1
Office Address P. O. Box 748, Salina, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-11-62 19
Application for plugging filed December 27, 1965 19
Application for plugging approved December 28, 1965 19
Plugging commenced March 8, 1966 19
Plugging completed March 11, 1966 19
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production June, 1963 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Mississippi Depth to top 4794 Bottom 4808 Total Depth of Well 5010 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-------------|---------|------|------|-------|--------|------------|
| Mississippi | Gas | 4792 | 4800 | 4 1/2 | 4854 | 4539 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
3-8-66 Filled with sand from 4500" to 4300". Run 3 sacks cement from 4300 to 4254'.
3-9-66 Shot at 4008', 3880' and 3780'. Working pipe
3-10-66 Shot at 3673', 3550' and started pipe
3-11-66 Set plug at 330'. Filled with rock to 320. Run 25 sacks of cement from 320' to 245'. Mudded from 245' to 40'. Rock and 10 sacks cement from 40' to base of celler. Cleaned up location and left..

REC
STATE CORP.
3-24-66
MAR 2

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address P. O. Box 156, Ellinwood, Kansas Permit #396

STATE OF KANSAS, COUNTY OF STAFFORD, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J. ...

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1966

Ozelle Sigler
Notary Public.

My commission expires October 22, 1967.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company. WESTERN PETROLEUM CO.
Farm. Davis No. 1

SEC. 10 T. 27 R. 19W
C NW NE

Total Depth. 5030'
Comm. 4-3-61 Comp. 4-25-61
Shot or Treated.
Contractor. Western Pet.
Issued. 9-16-61

County Kiowa
KANSAS



Elevation. 2260' RB

Production. 28 BOPD &
1,450,000 CFG

Figures Indicate Bottom of Formations.

| | |
|-------------------|----------|
| sand & clay | 95 |
| sand | 140 |
| red bed | 270 |
| shale | 321 |
| shale & clay | 480 |
| sand | 560 |
| red bed | 675 |
| sandy lime | 690 |
| shale & red bed | 810 |
| red bed & shale | 1247 |
| Anhydrite | 1275 |
| shale & shells | 2235 |
| shale & lime | 2370 |
| lime | 2815 |
| lime & shale | 3125 |
| shale & lime | 3270 |
| lime & shale | 3415 |
| shale & lime | 3583 |
| lime & shale | 3685 |
| shale & lime | 3760 |
| lime | 4030 |
| lime & shale | 4109 |
| lime | 4574 |
| cherty lime | 4587 |
| lime | 4795 |
| sand Conglomerate | 4807 |
| lime & chert | 4812 |
| cherty lime | 4845 |
| chert & lime | 4867 |
| lime & shale | 4921 |
| chert & shale | 5030 RFD |
| Total Depth | |
| TOPS: SCOUT | |
| Heebner | 4041 |
| Lansing | 4199 |
| Cherokee | 4701 |
| Mississippi | 4800 |

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION
Wichita, Kansas