


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 25 Twp. 27S Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C. SE NW
Lease Owner TGT Petroleum Corporation
Lease Name END WRENCH #2 Well No. #2
Office Address 209 E. William, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed May 7 1981
Application for plugging filed May 7 1981
Application for plugging approved May 7 1981
Plugging commenced May 7 1981
Plugging completed May 7 1981
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dwayne Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5030'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. @ 5030'
Set 1st Plug @ 628' with 50 sx.
Set 2nd Plug @ 350' with 30 sx.
Set 3rd Plug @ 40' Solid Bridge with 10 sx.
10 sx. in rathole, 2 sx. in water well.
50-50 posmix, 6% gel.

RECEIVED
STATE CORPORATION COMMISSION

Job was completed @ 4:30 a.m., 5/07/81.
State Plugger - Dwayne Rankin.

5-21-81
MAY 21 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc. CONSERVATION DIVISION
Wichita, Kansas


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1981

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



CONTRACTOR'S WELL LOG

OPERATOR:	TGT Petroleum Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	END WRENCH #2
LOCATION:	C SE NW, Section 25-27S-19W Kiowa County, Kansas
SPUD DATE:	4/18/81
COMPLETION DATE:	5/07/81

0	626	Sand
626	2076	Redbed and Shale
2076	4814	Lime & Shale
4814	4824	Mississippi
4824	5029	Lime & Shale
	5029	Rotary Total Depth

Spud 4/18/81. Cut 630' of a 12 1/4" hole. Ran 17 joints of 8 5/8" - 24# casing (tally 618.54') Set @ 628.54'. Cemented with 350 sx. of Halco Lite, 100 sacks of common cement. Cement did circulate. Plug was down @ 6:00 a.m., 4/18/81.

T.D. 5030'. Set 1st plug @ 628' with 50 sacks; Set 2nd Plug @ 350' with 30 sacks; Set 3rd Plug @ 40' Solid Bridge with 10 sx., 10 sx. in rathole, 2 sx. in water well, 50-50 posmix, 6% gel. Job was completed @ 4:30 a.m., 5/07/81. State Plugger - Dwayne Rankin.

SAMPLE TOPS:

Anhydrite 1160'
B/Anhydrite 1185'


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the END WRENCH #2, C SE NW, Section 25-27S-19W, Kiowa County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
ABERCROMBIE DRILLING, INC.
MAY 21 1981

CONSERVATION DIVISION
Wichita, Kansas
BY: Jack L. Partridge
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 19th day of May, 1981.



2/4/85

Suzanne M. Hofer
Suzanne M. Hofer, Notary Public