

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-025-20600 -00-00

LEASE NAME SO. MINNEOLA

TYPE OR PRINT

WELL NUMBER 1-2

NOTICE: Fill out **completely** and return to Cons. Div. office within 30 days
330 Ft. from S Section Line
990 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 8 TWP. 30S RGE. 25W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 7/3/82
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 12/19/01
Plugging Completed 12/19/01

The plugging proposal was approved on 12/19/01 (date)
by Steve Middleton w/KCC Dodge City, KS. (KCC District Agent's Name).
Is ACO-1 filed yes If not, is well log attached? no

Producing Formation ATOKA/MORROW Depth to Top 5320 Bottom 5330 TD 5400'
Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1402	8 5/8	1402	0
		production	5400	5 1/2		2600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Surface w/ 300# hulls. Pump 10 sxs Gel., 50 sx. Cement., 10 sx Gel, Pump 100# hulls. Release plug. Pumped 150 sx. 60/40 pos. 6% gel. Well P/A. Witnessed and approved by Steve Middleton w/ KCC Dodge City KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Ernie Morrison (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernie Morrison
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 28 th day of Dec, 2001

Notary Public - Barbara J. Dodson Barbara J. Dodson
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88

RECEIVED

JAN 04 2002

KCC WICHITA



JK
OK

file

Mike's Testing & Salvage Inc.

Invoice

P.O. Box 467
Chase, KS 67524

Date	Invoice #
12/27/2001	9241

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

USED FOR 036 P+A

APPROVED [Signature]

P.O. No.	Lease	County
	S.Minneola 1-2	Clark

Qty	Description	Rate	Amount
16	Hours Rig Time	120.00	1,920.00T
1	Shot	150.00	150.00T
3.5	Hours Welder	35.00	122.50T
1	5-1/2" Collar	48.00	48.00T
1	8-5/8" Collar	78.00	78.00T
2	Sacks Cement	10.50	21.00T
	12-10-01 Moved to location, set in rig and rigged up, checked hole, bridge plug @5266', dumped 2 sacks cement on top of plug, set in floor and rigged up, shot casing @2600', worked loose and pulled 5-1/2" up to 1000'. 9 Hours.		
	12-17-01 Drove to location. finished laying down 5-1/2", tore down and moved off. 7 Hours.		
	12-19-01 Allied Cementing plugged surface with 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, released 8-5/8" plug and 150 sx. cement. 60/40 pos, 6% gel. Plugging Complete. Sales Tax	5.90%	138.03

RECEIVED

Total

\$2,477.53

JAN 04 2002
KCC WICHITA