

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-025-20554 -00-00

LEASE NAME SO. MINNEOLA

WELL NUMBER 9-2

NOTICE: Fill out completely 1650 Ft. from S Section Line
and return to Cons. Div. 2970 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 8 TWP. 30S RGE. 25W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 2/82
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 12/19/01
Plugging Completed 12/19/01

The plugging proposal was approved on 12/19/01 (date)
by Steve Middleton w/KCC Dodge City, KS. (KCC District Agent's Name).
Is ACO-1 filed yes If not, is well log attached? no
Producing Formation MORROW Depth to Top 5056 Bottom 5310 TD 5400'
Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1421	8 5/8	1421	0
		production	5400	5 1/2		2600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Surface w/ 300# hulls. Pump 10 sxs Gel, . 50 sx. Cement., 10 sx Gel, Pump 100# hulls. Release plug, Pumped 150 sx. 60/40 pos. 6% gel. Well P/A. Witnessed and approved by Steve Middleton w/ KCC Dodge City KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .ss.

Ernie Morrison (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ernie Morrison
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 28 th day of Dec, 2001

Notary Public - Barbara J. Dodson Barbara Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88

RECEIVED
JAN 04 2002
KCC WICHITA



OK

file

Mike's Testing & Salvage Inc.

Invoice

P.O. Box 467
Chase, KS 67524

Date	Invoice #
12/27/2001	9242

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

USED FOR 036 P+A
 APPROVED AK BK

P.O. No.	Lease	County
	5 Minneola 9-2	Clark

Qty	Description	Rate	Amount
11	Hours Rig Time	120.00	1,320.00T
2	Shots	150.00	300.00T
2	Sacks Cement	10.50	21.00T
	Solvent	6.00	6.00T
3.5	Welder	35.00	122.50T
1	5-1/2" Collar	48.00	48.00T
1	8-5/8" Collar	78.00	78.00T
1	Night Out of Town Expense	135.00	135.00
	Thread Dope	25.00	25.00T
	12-12-01 Moved to location, set rig in.		
	12-13-01 Drove to location, rigged up, checked hole, bridge plug @5257', dumped 2 sx. cement on top of plug, set in floor and rigged up, shot pipe @2800' and 2600', worked pipe loose, layed down 5-1/2" casing. 11 Hours.		
	12-19-01 Allied Cementing plugged surface with 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, released 8-5/8" plug and 150 sx. cement. 60/40 pos, 6% gel. Plugging Complete.		
	Sales Tax	5.90%	113.31
RECEIVED JAN 04 2002 KCC WICHITA			
Total			\$2,168.81