

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-025-20837-00-00  
LEASE NAME MINNEOLA UNIT

TYPE OR PRINT

WELL NUMBER 9-1E

NOTICE: Fill out **completely** 400 Ft. from S Section Line  
and return to Cons. Div. 3380 Ft. from E Section Line  
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 4 TWP. 30S RGE. 25W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK  
PHONE # ( ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 10/18/84  
Character of Well WSW (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/8/02  
Plugging Completed 7/17/02

The plugging proposal was approved on 7/17/02 (date)  
by Steve Middleton w/KCC Dodge City, KS (KCC District Agent's Name).  
Is ACO-1 filed? YES If not, is well log attached? NO  
Producing Formation \_\_\_\_\_ Depth to Top 3578 Bottom 5386 TD 5500 Show depth and  
thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	633'	8 5/8	633	0
		production	5499'	4 1/2	5499	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Plugged well as follows: Set bridgeplug @ 3528' w/2 sxs cmt. on top. Shot csg 2700'. Plugged surface w/300# hulls, 10 sxs gel, 50 sxs cmt, 10 sxs gel, 100# hulls. Release plug and 150 sxs cmt. 60/40 pos 6% gel.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address  
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6 th day of August, 2002

Notary Public - Barbara J. Dodson [Signature]  
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED  
AUG 08 2002  
KCC WICHITA

OK

Mike's Testing & Salvage Inc.

P.O. Box 467  
Chase, KS 67524

Invoice

COPY	Date	Invoice #
	7/31/2002	9379

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

RECEIVED

AUG 01 2002

36 P/A/RK

P.O. No.	Lease	County
	Minneola 9-1E	Clark

Qty	Description	Rate	Amount
11	Hours Rig Time	120.00	1,320.00T
1	Shot	150.00	150.00T
2	Sacks Cement	10.50	21.00T
2	Hours - Welder	40.00	80.00T
	Solvent	6.00	6.00T
1	Night Out of Town Expense	135.00	135.00
	6-27-02 Log Tech set CIBP @3528'.		
	7-8-02 Moved in on location, rigged up, set in floor and rigged up, dumped 2 sacks cement on top of CIBP. Shot @2700', worked pipe loose, layed down 20 jts. 6 Hours.		
	7-9-02 Drove to location, finished laying down 4-1/2" casing. Tore down and moved off. 2 Hours.		
	7-16-02 Welder cut head off and welded 8-5/8" collar.		
	7-17-02 Allied plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and 150 sacks cement. 60/40 pos. 6% gel.		
	7-18-02 Drove to location, checked cement, was down 130 ft. Cut 8-5/8" off and ran ready-mix to the top. 3 Hours.		
	Sales Tax	6.30%	99.35
<b>Total</b>			<b>\$1,811.35</b>

RECEIVED

AUG 08 2002

KCC WICHITA