

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-025-20890 -00-00
LEASE NAME MINNEOLA UNIT(Norton 1-4)

TYPE OR PRINT WELL NUMBER 9-1

NOTICE: Fill out completely ~~4290~~ ⁹⁹⁰ Ft. from S Section Line
and return to Cons. Div. 3330 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 4 TWP. 30S RGE25W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY CLARK
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/22/85
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/9/02
Plugging Completed 7/9/02

The plugging proposal was approved on 7/9/02 (date)
by STEVE MIDDLETON w/KCC DODGE CITY, KS. (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? no
Producing Formation MORROW Depth to Top 5288 Bottom 55293 TD 5423'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1114	8 5/8	1114	0
		production	5416	5 1/2	5416	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Allied set cement plugs. Shot pipe @ 2700'. Welded 85/8" collar on. Plugged surface w/300#hulls, 10 sxs gel, 50sxs cement, 10sxs gel, 100#hulls, released plu & 150 sxs 60/40 pos. 6%gel. Well P/A. Witnessed and approved by STEVE MIDDLETON w/ KCC DODGE CITY, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 19 th day of July, 2002

Notary Public - Barbara J. Dodson

My Commission Expires: 12/16/03 eForm CR-43 Revised 05-88



RECEIVED
JUL 22 2002
KCC WICHITA

Handwritten initials or mark.

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

RECEIVED

JUL 19 2002

Date	Invoice #
7/18/2002	9370

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

RECEIVED
JUL 22 2002
KCC WICHITA

RA 36/RK

P.O. No.	Lease	County
	Minneola 9-1	Clark

Qty	Description	Rate	Amount
14	Hours Rig Time	120.00	1,680.00T
1	Shot	150.00	150.00T
2	Hours - Truck Move Floor	50.00	100.00T
2	Sacks Cement	10.50	21.00T
	Solvent	6.00	6.00T
3	Hours Welder	40.00	120.00T
1	8-5/8" Collar	60.00	60.00T
	6-27-02 Drove to location, Log Tech set CIBP @5238', 1 Hour		
	7-3-02 Set rig in on location, rigged up, set in floor and rigged up, ran 2 sacks of cement on top of CIBP @5238. 8 Hours.		
	7-7-02 Welder cut off head and welded 8-5/8" collar on.		
	7-8-02 Drove to location, shot pipe loose @2700', layed down casing. Tore down and moved off.		
	7-9-02 Allied Cementing plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and 150 sacks cement, 60/40 pos, 6% gel. Plugging Complete.		
	7-16-02 Welder cut 8-5/8" collar off and cut out dutchman.		
	Sales Tax	6.30%	134.63
		Total	\$2,271.63

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# 48-0727860

 * INVOICE *

RECEIVED

Invoice Number: 087571

JUL 15 2002

Invoice Date: 07/11/02

COPY

Sold Murfin Drilling Co.
 To: 250 N. Water, St. #300
 Wichita, KS
 67202

RECEIVED
 JUL 22 2002
 KCC WICHITA

Cust I.D.....: Murfin
 P.O. Number...: Minneola 9-1
 P.O. Date.....: 07/11/02

Due Date.: 08/10/02
 Terms.....: Net 30

30
 RJA/RK

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	120.00	SKS	6.6500	798.00	T
Pozmix	80.00	SKS	3.5500	284.00	T
Gel	30.00	SKS	10.0000	300.00	T
Hulls	4.00	SKS	18.0000	72.00	T
Handling	234.00	SKS	1.1000	257.40	T
Mileage (60)	60.00	MILE	9.3600	561.60	T
234 sks @\$.04 per sk per mi					
Plug	1.00	JOB	225.0000	225.00	T
Wooden plug	1.00	EACH	23.0000	23.00	T

All Prices Are Net, Payable 30 Days Following Subtotal: 2521.00
 Date of Invoice. 1 1/2% Charged Thereafter. Tax.....: 171.43
 If Account CURRENT take Discount of \$ 252.10 Payments: 0.00
 ONLY if paid within 30 days from Invoice Date Total....: 2692.43

ALLIED CEMENTING CO., INC. 10510

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <i>7-9-02</i>	SEC <i>4</i>	TWP. <i>30s</i>	RANGE <i>25w</i>	CALLED OUT <i>5:00 AM</i>	ON LOCATION <i>12:00 pm</i>	JOB START <i>2:45 pm</i>	JOB FINISH <i>2:45 pm</i>
LEASE <i>Minneola</i>		WELL# <i>9-1</i>	LOCATION <i>Minneola W, W, 1/2, 1/2</i>		COUNTY <i>Clark</i>	STATE <i>Ks</i>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR *MT+S*

TYPE OF JOB *OHF*

HOLE SIZE	T.D.
CASING SIZE <i>8 7/8</i>	DEPTH <i>1114'</i>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <i>600</i>	MINIMUM
MEAS. LINE	SHOE JOINT

CEMENT LEFT IN CSG.

PERES. *shut in 200 PSI*

DISPLACEMENT

OWNER *Murfin Drilling Co.*

CEMENT AMOUNT ORDERED

200 5x 80:40:6

20 5x Gel 400' Halls

COMMON	<i>120</i>	@	<i>6.65</i>	<i>798.00</i>
POZMIX	<i>80</i>	@	<i>3.55</i>	<i>284.00</i>
GEL	<i>30</i>	@	<i>10.00</i>	<i>300.00</i>
CHLORIDE		@		
<i>Halls - 4</i>		@	<i>18.00</i>	<i>72.00</i>
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>234</i>	@	<i>1.10</i>	<i>257.40</i>
MILEAGE	<i>60</i>			<i>561.60</i>

TOTAL \$ *2273.00*

RECEIVED
JUL 22 2002
KCC WICHITA

EQUIPMENT

PUMP TRUCK # <i>368281</i>	CEMENTER <i>Carl Baldwin</i>
BULK TRUCK # <i>240</i>	HELPER <i>Steve Davis</i>
BULK TRUCK #	DRIVER <i>Dave Felio</i>
BULK TRUCK #	DRIVER

REMARKS:

Pump 300' Halls

10 5x Gel

50 5x Cement

10 5x Gel

100' Halls

Release plug

150 5x Cement, (shut in)

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<i>225.00</i>
EXTRA FOOTAGE	@
MILEAGE <i>60</i>	@ <i>3.00</i> <i>N/C</i>
PLUG <i>wooden</i>	@ <i>23.00</i> <i>23.00</i>
	@
	@

TOTAL \$ *248.00*

CHARGE TO: *Murfin Drilling Co.*

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \$ *171.43*

TOTAL CHARGE \$ *2692.43*

DISCOUNT \$ *252.10* IF PAID IN 30 DAYS

SIGNATURE *Monte J. Anderson*

Monte J. Anderson
PRINTED NAME