

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-025-20617 -00-01

LEASE NAME SO. MINNEOLA

TYPE OR PRINT

WELL NUMBER 5-1

NOTICE: Fill out completely 4785 Ft. from S. Section Line

and return to Cons. Div. 4785 Ft. from E Section Line

office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC 16 TWP. 30S RGE. 25W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY Clark

PHONE # () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 10/12/82

Character of Well oil (Oil, Gas, D&A, Input, Water Supply Well)

Plugging commenced 12/19/01

EOR Per CP 973

Plugging Completed 12/19/01

The plugging proposal was approved on 12/19/01 (date)
by Steve Middleton w/KCC Dodge City, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Morrow Depth to Top 5316 Bottom 5325 TD 5500' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1427	8 5/8	1427'	0
		production	5500'	5 1/2		2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: surface w/ 300# hulls, 10 sx. Gel, 50 sx. Cement, 10 sx. Gel, 100# hulls, released 8 5/8' plug and 150 sxs. cement 60/40 pos, 6% gel. Approved by Steve Middleton w/ KCC Dodge City, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Ernie Morrison (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernie Morrison
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 2nd day of Jan, 2002

Notary Public - Barbara J. Dodson Barbara J. Dodson
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88

RECEIVED
1-9-2002
JAN 04 2002
KCC WICHITA



52

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

file

Invoice

Date	Invoice #
12/27/2001	9243

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

USED FOR 036 P&A
APPROVED [Signature]

P.O. No.	Lease	County
	S.Minneola 5-4	Clark

Qty	Description	Rate	Amount
13	Hours Rig Time	120.00	1,560.00T
2	Shots	150.00	300.00T
2	Sacks Cement	10.50	21.00T
	Solvent	6.00	6.00T
3.5	Hours Welder	35.00	122.50T
1	5-1/2" Collar	48.00	48.00T
1	8-5/8" Collar	78.00	78.00T
2	Nights Out of Town Expense	135.00	270.00
	12-17-01 Moved to location, set in rig and rigged up, checked hole, bridge plug @5266', dumped 2 sacks cement on top of plug. 3 Hours.		
	12-18-01 Drove to location, set in floor and rigged up, shot casing @2600' and 2430', worked pipe loose, layed down 5-1/2" casing. 10 Hours.		
	12-19-01 Allied Cementing plugged surface with 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, released 8-5/8" plug and 150 sx. cement. 60/40 pos, 6% gel. Plugging Complete.		
	Sales Tax	5.90%	125.99

RECEIVED	Total	\$2,531.49
-----------------	--------------	------------

JAN 04 2002
NCC WICHITA