

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
10 S. Market, Room 207B  
Wichita, KS 67202

WELL PLUGGING RETURN  
K.A.R.-02-3-117

API NUMBER 15-025-20,239-00-00

LEASE NAME Giles "B"

WELL NUMBER 3

2970 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 25 TWP. 30S RGE. 22W (E) or (W)

COUNTY Clark

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-17-01

Plugging Completed 7-18-01

RECEIVED

TYPE OR PRINT

8-16-2001

AUG 16 2001

NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

EASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS 100 S. Main, Suite 505, Wichita, Kansas 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 5351'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	530'	None
				4-1/2"	5336'	3807'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side.  
Plugged off bottom with sand to 5200' and 4 sks. cement. Shot pipe @3807', pulled up to 1200', pumped 10 sks. gel and 50 sks. cement, pulled up to 500', pumped 50 sks. cement, pulled up to 40', pumped 20 sks. cement, 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of August, 2001

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



[Handwritten initials]