

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-009-04888-000

LEASE NAME Buckbee

WELL NUMBER 3

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 15 TWP. 20 RGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed         

Plugging Commenced 11-2-00

Plugging Completed 11-3-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DJ Oil Operations

ADDRESS 305 E. 6th Ellinwood, Kansas 67526

PHONE (316) 564-2759 OPERATORS LICENSE NO. 31199

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Jay Pfiefer (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3419'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RCO 11-16-2000

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	180'	None
				5-1/2"	3375'	210'

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 2000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement were used, state the character of same and depth placed, from          feet to          feet. 5-1/2" casing into @210' layed casing down. Ran 2" tubing to 1433', pumped 100 sks. cement, pulled to 650', pumped 40 sks. cement, pulled to 250', pumped 110 sks. cement, pulled 3 Jts. tubing and circulated 70 sks. cement to surface. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DJ Oil Operations

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed to  
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of November, 2000

[Signature]  
Notary Public

My Commission Expires:         



[Signature]  
Form CP  
Revised 05-