

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Topeka, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-22,964-00-00

LEASE NAME Fisher

WELL NUMBER 1-31

1320 Ft. from S Section Line

660 Ft. from ~~S~~ Section Line

SEC. 31 TWP. 19S RGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-29-00

Plugging Completed 3-1-00

RECEIVED  
KANSAS CORP COM  
3-13-2000  
2000 MAR 13 12:10  
TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR K & N Petroleum, Inc.

ADDRESS 513 W. 6th Street Ellinwood, Kansas 67526

PHONE# (316) 564-3422 OPERATORS LICENSE NO. 3208

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	576'	None
				5-1/2"	3418'	2430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. Plugged off bottom with sand to 3300' and 5 sks. cement shot pipe @2430', pulled up to 1320'. Pumped 100 sks. cement w/300# hulls, pulled up to 580', pumped 50 sks. cement w/100# hulls, pulled up to 250' and circulated cement to the surface with 50 sks. 60/40 pos, 10% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: K & N Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 10th day of March, 2000

Irene Herberg  
Notary Public

My Commission Expires: \_\_\_\_\_



Form 07  
Revised 05-