

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-009-23,839-00-00

LEASE NAME Schartz

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-24

2970' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 24 TWP. 20SRGE. 13W (E) or (W)

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. St. N. Bldg. 300 Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

COUNTY Barton

Date Well Completed

Character of Well Oil

Plugging Commenced 11-22-00

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Plugging Completed 11-27-00

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (XCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	306'	None
				4-1/2"	3599'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each str. Plugged off bottom with sand to 3150' and 4 sks. cement. Shot pipe @2400', 2000', 1800', pulled up to 1350', pumped 65 sks. cement and 300# hulls, pulled up to 700', pumped 40 sks. cement and 200# hulls, pulled 20 250', pumped 55 sks. cement and circulated to surface, 60/40 nos. 6% gel Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

12-4-2000

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

REC 4 2000

Mike Kelso

(Employee of Operator or Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.


(Signature)

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of November, 2000

Notary Public

My Commission Expires:



Form CP Revised 05-