

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-23614-00-00

LEASE NAME SEYFERT

WELL NUMBER #1

2640 Ft. from S Section L

2310 Ft. from E Section L

SEC. 35 TWP. 19 RGE. 12 or

COUNTY BARTON

Date Well Completed 7-84

Plugging Commenced 9-14-00

Plugging Completed 9-14-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE OPERATOR L. D. DRILLING, INC.

ADDRESS R.R. 1 BOX 183 B GREAT BEND, KANSAS 67530

PHONE (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 14, 2000 (date)

by Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation arbuckle Depth to Top \_\_\_\_\_ Bottom T.D. 3430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface production	not available	0	3429	5 1/2"	3429	500' pipe no good left the rest

Describe in detail the manner in which the well was plugged, indicating where the mud flu placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each

1st Plug: 2 3/8" tubing hanging at 725' in 5 1/2" and 8 5/8" Mixed 220 sx 60/40 Poz 10% gel W/400# hulls to circulate cement; pull tubing out of hole swedge up to 8 5/8" mix 55 sx. 60/40 poz 10% gel 300# 100# shut in press.  
Total 275 sx. 60/40 pozmix 10% gel 400# hulls

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P.O. BOX 31 Russell, Kansas 67667

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss. WICHITA, KS

Bessie (Employee of Operator) or Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as if the same are true and correct, so help me God.

(Signature) Bessie Dewert  
Bessie Dewert

(Address) R.R. 1 Box 183 B Great Bend Ks. 67530

SUBSCRIBED AND SWORN TO before me this 21st day of December, 2000.

Rashell Patten  
Notary Public

My Commission Expires: 2-02-03 Rashell Patten

