

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-009-04216-0000

LEASE NAME Drews B/A

WELL NUMBER 4

330 Ft. from S Section Line

2310 Ft. from <sup>W</sup> Section Line

SEC. 15 TWP. 18S RGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed 1952

Plugging Commenced 5-15-00

Plugging Completed 5-16-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188 Wichita, Kansas 67278-3188

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3322'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	280'	None
				5-1/2"	3310'	1801'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Plugged off bottom with sand to 2800' and 5 sks. cement, shot pipe @1801', pulled up to 1380', pumped 200# hulls and 125 sks. cement, pulled to 600', pumped 50 sks. cement and 200# hulls, pulled to 280', circulated 65 sks. cement 60/40pos, 10% gel pulled rest of pipe. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

MAY 22 2000

Mike Kelso (Employee of Operator) Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of May, 2000

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 2001

Form CP  
Revised 05-