

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-16519-00-00

LEASE NAME Eveleigh "P"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2,970 Ft. from S Section Line

4,290 Ft. from E Section Line

SEC. 03 TWP. 18 RGE. 13 ~~W~~ or (W)

COUNTY Barton

Date Well Completed 1945

Plugging Commenced 8/02/00

Plugging Completed 8/02/00

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS P. O. Box 698 Great Bend, Kansas 67530

PHONE#(316) 792-2506 OPERATORS LICENSE NO. 5310

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 14, 2000 (date)

by Mr. Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? N. A. If not, is well log attached? N. A.

Producing Formation Lansing-K. C. Depth to Top 3,154' Bottom 3,328' T.D. P. B. 3,342'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	844'	None
				5 1/2"	3,378'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Allied Cementing pumped 20 sacks 60/40 pozmix with 10% gel down 5 1/2" casing followed by 160 sacks cement blended with 500# hulls and topped with 45 sacks cement. shut in at 500psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address P. O. Box 698 Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: James W. Rockhold

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold


(Address) P. O. Box 698

Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 31 day of August, 19 2000

Angie Crawford

My Commission Expires: 10-7-03



UD

RECEIVED
STATE CORPORATION COMMISSION

SEP 01 2000

CONSERVATION DIVISION
Wichita, Kansas