

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,594-0000

LEASE NAME Apt

WELL NUMBER 1

2970 Ft. from S Section Lin

2310 Ft. from E Section Lin

SEC. 30 TWP. 27 RGE. 13 (X or W)

COUNTY Pratt

Date Well Completed 5-7-85

Plugging Commenced 8-4-92

Plugging Completed 11:45 AM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-4-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Viola Depth to Top 3877 Bottom 3887 T.D. 4503

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	429	0
				5 1/2	4503	2238

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each
Bottom plug: Sanded to 3820 & bailed 5 sx Cement.

Top plug: Pumped 300 lbs Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lbs Hulls, 100 sx Cement - 60/40 w/6% Gel, Pressure 300 lbs maximum & 100 lbs shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1992



Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
AUG 6 1992
RESERVATION DIVISION
Form C
Revised 05