

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,081-0003

LEASE NAME Apt

WELL NUMBER 2

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 30 TWP. 27 RGE. 13 XXX (Section)

COUNTY Pratt

Date Well Completed NA

Plugging Commenced 8-4-92

Plugging Completed 12:45 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-4-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation NA Depth to Top 4312 Bottom 4327 T.D. 4529

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	428	0
				4 1/2	4528	2132

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from ___ feet to ___ feet each. Bottom plug: Sanded to 4260 & bailed 4 sx Cement.

Top plug: Pumped 300 lb Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lbs Hulls, 8 5/8 Wiper plug, 100 sx Cement, 60/40 w/6% Gel, 400 lbs maximum pressure & 225 lbs shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1992



Anna K. Burke
Notary Public

Expires: 4-30-96

RESERVATION DIVISION
Wichita, Kansas
Form C
Revised 05