

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-121-02623-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
3679 Feet from N / S Line of Section
1163 Feet from E / W Line of Section
 GPS: Lat: 38.618049 Long: 95.032389 Date: 8/18/14 8/8/13
 Lease Name: Tarr II Well #: 6-2 (T62)
 County: Miami Total Vertical Depth: 615 feet

(L.S.)

Operator License No:	String	Size	Depth	Pulled	Comments
<u>101</u>	<u>DRIVE - Drive Pipe</u>	<u>10.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
<u>Op Name: STATE OF KANSAS</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
<u>Address 1: 130 S. MARKET</u>	<u>T2 - Tubing 2</u>	<u>1.500</u>	<u>400</u>	<u>0</u>	<u>EST.</u>
<u>Address 2:</u>					
<u>City: WICHITA</u>					
<u>State: KS</u> Zip Code: <u>67202</u>					

Well Type: OG - Oil & Gas (-oil) UIC Docket No.: _____ Date/Time to Plug: 7/21/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Revd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 7/21/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:

Run 1" inside 2" and hit soft cement. Plugged 1" and beat 1" through soft cement. Pull out 1" and unplug it. Run 1" back and run to 615 ft and hit mud. Run 3/4" inside 1 1/2" pipe and hit cement at 20 ft. Beat through and run pipe to 240 ft. Hit mud. Run 1" outside 2" to 325 ft and hit mud. Try to wash 3/4" deeper but it was plugged. Pull out and unplug, run back and wash to 400 ft. Wash 1" inside 2" but couldn't get deeper. Wash 1" outside 2" to 400 ft. Pump Portland cement from TD to surface inside 1 1/2", 2" and outside both to surface. Pull pipe and top off well. Pump total of 221 sacks of cement. Well plugged.

Perfs:	Top	Bottom	Thru
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-037. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03

Received
KANSAS CORPORATION COMMISSION
SEP 04 2014
CONSERVATION DIVISION
WICHITA, KS

Frank Guilfoyle
(Technician)

Form: District Plugging Report - _____