

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-121-02626-0000  
 Spot: NWSENE Sec 36 Twp 16 S Rng 21  E /  W  
3813 Feet from  N /  S Line of Section  
899 Feet from  E /  W Line of Section  
 GPS: Lat: 38.618410 Long: 95.031429 Date: 8/28/14 8/8/13  
 Lease Name: Tarr II Well #: 6-6 (T66)  
 County: Miami Total Vertical Depth: 690 feet

(L.S.)

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>266 N. Main St. Ste. 220</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>690</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	<u>PKR - Packer</u>	<u>1.000</u>	<u>450</u>	<u>450</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 8/11/14 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Revd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed  
Plugging  
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 8/11/14 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Run 1" tap and screw into 1" pipe. Pull packer loose and pull to 150 ft where it hangs up and and parts 1" at packer. Run 1" back to 150 ft with tap and screw into packer. Work packer loose and pull out a plug packer. Run 1" inside 2" to 650 ft. Wash 1" outside 2" to 410 ft and hit hard. Pump Portland cement from TD to surface inside 2" and outside 2". Pull pipe and top off well. Pump 218 sacks of cement. Well plugged.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-038. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
 Received  
 KANSAS CORPORATION COMMISSION  
**SEP 04 2014**  
 CONSERVATION DIVISION  
 WICHITA, KS

Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_