

**Kansas Corporation Commission
District Plugging Report**

API Well Number: 15-121-02627-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
3870 Feet from N / S Line of Section
1298 Feet from E / W Line of Section
 GPS: Lat: 38.618579 Long: 95.032859 Date: 10/2/14 8/8/13
 Lease Name: Tarr II Well #: 7-2 (T72)
 County: Miami Total Vertical Depth: 700 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>10.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>226 N. Main St. St. 220</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____	_____	_____	_____	_____	_____

Well Type: ~~SWD - Water Injection - Disposal~~ EOR (Per Frank) UIC Docket No.: E-01521 Date/Time to Plug: 8/22/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Recvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 8/22/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Screw 1" and tap into 1" inside of 2". Work 1" loose and pull 550 ft of 1" with packer. Run 1" back to 560 ft and could not wash deeper. Run 1" outside 2" to 325 ft and wash to 350 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 176 sacks of cement. Well plugged.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-040. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 RECEIVED KANSAS CORPORATION COMMISSION Frank Guilfoyle (Technician)
 OCT 03 2014 10-3-2014 CONSERVATION DIVISION WICHITA, KS Form: District Plugging Report - _____