

API Well Number: 15-121-02628-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
3934 Feet from N / S Line of Section
1152 Feet from E / W Line of Section
 GPS: Lat: 38.618749 Long: 95.032349 Date: 12/3/14 8/8/13
 Lease Name: (L.S.) Tarr II Well #: 7-4 (T-74)
 County: Miami Total Vertical Depth: 700 feet

Kansas Corporation Commission
District Plugging Report

Operator License No: 101
 Op Name: STATE OF KANSAS
 Address 1: 226 N. Main St. St. 220
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - _____

String	Size	Depth	Pulled	Comments
<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
<u>TI - Tubing I</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E-01521 Date/Time to Plug: 10/29/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kipley Company Name: KWS Phone: (620) 431-8945

Proposed
 Plugging
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 10/29/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:

Perfs:	Top	Bottom	Thru
Move equipment to location. Try to get 1" inside 2", only got to 75 ft and hit hard. Try to wash through but couldn't. Pull 1" out and 2" parts 12 ft down. Skirt over 2" with swedge. Run 1" to 335 ft inside 2". Wash 1" outside 2" to 550 ft. Wash 1" inside 2" to 525 ft and hit hard. Pump Portland cement to surface inside and outside 2". Pull pipe and top off well. Pump total of 202 sacks of cement. Well plugged.	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____
	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-041. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 **KCC WICHITA** Frank Guilfoyle
 (Technician)
 Form: District Plugging Report --
 JAN 05 2015
 RECEIVED