

District Plugging Report

Spot: SWNE Sec 36 Twp 16 S Rng 21 ☒ E / ☐ W
4107 Feet from ☐ N / ☒ S Line of Section
1303 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.619229 Long: 95.032879 Date: 10/27/14 8/8/13
 Lease Name: Farr II Well #: 8-3 (T83)
 County: Miami Total Vertical Depth: 510 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>266 N. Main St. Ste. 220</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>510</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>	_____	_____	_____	_____	_____

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: _____ Date/Time to Plug: 8/26/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

**Proposed
Plugging
Report:**

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%

Date/Time Plugging Completed: 8/26/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
-------------------------	--------	-----	--------	------

Run 1" inside 2" to 150 ft and hit hard. Pull 1" and put on 1" tap. Run back and couldn't screw into anything. Try to wash but pressures up. Pull out, remove tap and run back to 150 ft. Run 1" outside 2" to 300 ft and wash to 510 ft. Pump Portland cement to surface inside and outside 2". Pull pipe and top off well. Pump total of 104 sacks of cement. Well plugged.

[illegible]

Remarks	Contract # 39389. Control # 20140052-043. Regular section. GPS'ed by FG in NAD 83. Category II.
---------	---

Plugged Thru: TBG - Tubing

RECEIVED
KANSAS CORPORATION COMMISSION

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

OCT 03 2014
10-3-2014
CONSERVATION DIVISION
WICHITA, KS

Frank Guilford
(Technician)

Form: District Plugging Report –