

API Well Number: 15-121-02632-0000  
 Spot: SWNE Sec 36 Twp 16 S Rng 21  E /  W  
4229 Feet from  N /  S Line of Section  
1146 Feet from  E /  W Line of Section  
 GPS: Lat: 38.619559 Long: -95.033290 Date: 10/23/14 8/8/13  
 Lease Name: Tarr II Well #: 8-6 (T86)  
 County: Miami Total Vertical Depth: 700 feet

**Kansas Corporation Commission**  
**District Plugging Report**

Operator License No: 101  
 Op Name: STATE OF KANSAS  
 Address 1: 266 N. Main St. Ste. 220  
 Address 2:  
 City: WICHITA  
 State: KS Zip Code: 67202 - 1513

String	Size	Depth	Pulled	Comments
<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
<u>T2 - Tubing 2</u>	<u>1.000</u>	<u>700</u>	<u>500</u>	<u>EST.</u>

Well Type: OG - Oil & Gas (oil) UIC Docket No.: Date/Time to Plug: 9/25/14 /  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed  
 Plugging  
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 9/25/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report: Perfs: Top Bottom Thru

Move equipment to location. Screw 1" and tap into 1" inside 2". 1" parts at first collar. Run 1" and tap back down 2" and screw into 1". Work pipe and parts again. Pull 13 joints of 1" out. Run 1" and tap back to 285 ft and screw into 1", tap keeps pulling out of stump. Pull 1" and tap out. Run left-hand 1" and tap back. Back off pipe and pull out 8 more joints. Run left-hand back, back off 1" and pull 2 joints of 1" out. Run 1" open ended back to 500 ft inside 2". Run 1" outside 2" to 375 ft and hit mud. Wash 1" outside 2" to 535 ft. Pump Portland cement from TD to surface inside and outside 2". Pull pipe and top off well. Pump total of 215 sacks of cement. Well plugged.

Perfs:	Top	Bottom	Thru
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 NOV 05 2014 11-5-2014  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks: Contract # 39389. Control # 20140052-045. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_