

API Well Number: 15-121-02436-0000  
 Spot: SWNE Sec 36 Twp 16 S Rng 21  E /  W  
4442 Feet from  N /  S Line of Section  
1300 Feet from  E /  W Line of Section  
 GPS: Lat: 38.620149 Long: 95.032870 Date: 10/22/14 8/8/13  
 Lease Name: Tarr Well #: 9-6 (T96)  
 County: Miami Total Vertical Depth: 700 feet

**Kansas Corporation Commission**  
**District Plugging Report**

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>10.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>226 N. Main St. St. 220</u>	<u>T1 - Tubing 1</u>	<u>4.500</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	<u>T2 - Tubing 2</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____	_____	_____	_____	_____	_____

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E-01521 Date/Time to Plug: 9/23/14 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed  
 Plugging  
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 9/23/14 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Dig out surface. Dig deeper to try to cut 4.5" to see if there is cement between the 4.5" and 2". There is. Reset surface. Run 1" and reamer down 2" to 450 ft. Pull out to perforate. Run 1" to 450 ft inside 2". Wash to 575 ft. Run 1" outside 4.5" to 250 ft, wash to 360 ft and hit hard. Pump Portland cement from TD to surface. Pull pipe and top off well. Pump total of 169 sacks of cement. Well plugged.		<u>75</u>	<u>350</u>	<u>TBG - Tubing</u>
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____
		_____	_____	_____

RECEIVED  
 KANSAS CORPORATION COMMISSION  
NOV 05 2014  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks: Contract # 39389. Control # 20140052-050. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
 \_\_\_\_\_  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_