

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02621-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
3564 Feet from N / S Line of Section
1061 Feet from E / W Line of Section
 GPS: Lat: 38.617730 Long: 95.032030 Date: 12/3/14 9/26/14
 Lease Name: Tarr II Well #: T101
 County: Miami Total Vertical Depth: 215 feet

Operator License No: 101 String _____ Size _____ Depth _____ Pulled _____ Comments _____
 Op Name: STATE OF KANSAS DRIVE - Drive Pipe 10.000 15 0 EST.
 Address 1: 266 N. Main St. Ste. 220
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: LH - Lost Hole, possible water well (oil) Per Franko UIC Docket No.: _____ Date/Time to Plug: 10/24/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 10/24/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Run 4.5" swedge to 80 ft and hit. Pull out and put on 2.5" swedge. Run to 80 ft and hit. Pull out and remove swedge. Run 1" open to 80 ft and hit again. Wash 1" through several bridged areas and hit hard at 215 ft. Just got rusty water to return, possible old water well. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 72 sacks of cement. Well plugged.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-053. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 KCC WICHITA Frank Guilfoyle (Technician)
 Form: District Plugging Report - _____
 JAN 05 2015
 1-5-2015 RECEIVED