

To: 1 040683
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-4

API NUMBER 15- 151-21,594-0000 230
NW SW NE, SEC. 30, T. 27 S, R. 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers Inc.
Name & Address P.O. Box 251
Great Bend, KS 67530

3630 feet from S section line
2310 feet from E section line
Lease Name Apt _____ Well # 1
County Pratt 146.34
Well Total Depth 4503 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 4 Month: 8 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

were: 5 1/2" at 4503' w/225 sx cement, PBD 3900', Perfs at 3877-87'
1st plug sand back to 3827' and dump 5 sx cement on top of sand through bailer.
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 4 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3827' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

ACD 8-13-92 AUG 15 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2237.8' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form. - Wichita, Kansas)

INVOICED
I did (or observe) this plugging.
DATE 8-20-92
INV. NO. 35991

Signed Stephen J. Pfeifer
(TECHNICIAN)