

To: 1 040682
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,081-0000 TJR
SW NW NE, SEC. 30, T. 27 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers Inc.
Name & Address P.O. Box 251
Great Bend, KS 67530

4290 feet from S section line
2310 feet from E section line
Lease Name Apt _____ Well # 2
County Pratt 147.19
Well Total Depth 4529 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 4 Month: 8 Year: 1992

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" casing, Perfs at 4312-27
1st plug sand back to 4260' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:45 p.m. Day: 4 Month: 8 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4260' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 400 psi and shut in 225 psi.

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1992
8-13-92

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2132.10' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 8-20-92
INV. NO. 35992

Signed Stephen J. Pfeifer
(TECHNICIAN)