

To: **1 040261**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635

Operator: Great Bend Casing Pullers
Name & Address P.O. Box 768
Great Bend, KS 67530

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 4 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4538' Perfs at 4300-4307'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

4-11-89

APR 11 1989

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations Attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3 p.m. Day: 6 Month: 4 Year: 19 89
Plate welded in top of 8 5/8" with 2" collar to pump through.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx gel, and 100 lbs. hulls, pumped hole in surface pipe. After repairs were made, dug out cellar, didn't find hole in surface pipe, ragged off hole in surface pipe with gunny sack strips and 50 lbs. hulls, pumped in 95 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2750' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

DATE 4-24-89

INV. NO. 24443

Signed Stephen J. Pfeiffer
(TECHNICIAN)