



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 15 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Red Hickman of Stickle Drilling Company has this date requested permission to plug the following described well:

Mr. Hickman guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 321 West Douglas, Wichita, Kansas

Lease Name: Parton Well No. # 2

Location: C NE SE Sec. 3 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 4410 Oil Well

Gas Well Input Well SWD Well D & A  Lost Hole

Mr. Hickman was instructed to plug the well as follows:

316' of 8 5/8" surface pipe, cemented with 300 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat and mouse hole with 5 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent