

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

OCT -2 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed September 19, 1967.

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Inc. has this
date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Gabbert-Jones, Inc.

Complete Address: 830 Sutton Place, Wichita, Kansas 67202

Lease Name: Ernest Davis Well No. # 1

Location: C N/2 NE Sec. 10 Twp. 27 Rge. 19 (E) (W) W

County Kiowa Total Depth 4833' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

333' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Arlene Elving
Conservation Division Agent