

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickrell Drlg Co has this
date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg & Southwest Petro-Chem

Complete Address: 705 4th Natl Bldg Wichita, KS

Lease Name: Parton B Well No. 1

Location: C NE/NE Sec. 7 Twp. 27S Rge. 19 (E)(W) W

County: Kiowa Total Depth 4852 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. French was instructed to plug the well as follows:

222 ft 8 5/8 surface cemented with 190 sacks. Pump plug.
40 sacks cement to 500 ft. 2nd plug at 200 ft, 25 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Allied Cementing Co Great Bend, KS

Very truly yours,

H. Russell Beherster
Conservation Division Agent